

**PACK-UP INSTRUCTIONS  
FOR PRE-INSTALLED ITEMS**

- 1) ITEMS BELOW APPLY TO THIS SHIPMENT.
- A) REMOVE AND PACK THE FOLLOWING LIGHTING ITEMS:
- | QTY. | LIGHT BULBS           | QTY. | ACCESSORIES       |
|------|-----------------------|------|-------------------|
| ---  | FLUORESCENT           | ---  | LENS, WIRE GUARD  |
| ---  | INTERIOR INCANDESCENT | ---  | WIRE GUARD        |
| 1    | EXTERIOR LIGHT        | ---  | EXTERIOR LENS     |
| 1    | GENERATOR RECEPTACLE  | 1    | POWER ENTRY ELBOW |
- B)
- C) REMOVE AND PACK THE FOLLOWING ITEMS WITH HARDWARE:
- | QTY. | DESCRIPTION |
|------|-------------|
| ---  | ---         |
| ---  | ---         |
- D) SECURE 1 (QTY.) STEEL DOOR(S) WITH DEADBOLT.
- E) EQUIPMENT WARRANTIES AND OTHER PERTINENT INFORMATION IN LITERATURE HOLDER.
- F) INSTALL TRANSPORTATION TAG PER DRAWING N-009-1.
- G) THIRD PARTY INSPECTION SIGNAGE TO BE INSTALLED ON OUTSIDE OF DISTRIBUTION PANEL (IF REQUIRED).
- H) INSTALL ANDREW DATA PLATE ON OUTSIDE OF DISTRIBUTION PANEL.
- I) DISCONNECT BATTERIES IN FM-200 CONTROL PANEL TO PREVENT BATTERY DISCHARGE. REMOVE HALON ACTUATOR FROM TANK TO PREVENT DISCHARGE.
- 2) DRAWINGS IN DRAWING LIST MARKED WITH AN ASTERISK (\*) ARE TO BE INCLUDED IN THE SHELTER PACK-UP MATERIALS.
- 3) PLACE ALL PACK-UP MATERIALS AS CLOSE TO DOOR AS POSSIBLE.
- 4) SEAL ALL OPENINGS PRIOR TO SHIPMENT.

REV.	DESCRIPTION	DATE	APPROVED
TS	APPROVAL ISSUE		

**DRAWING LIST**

REV. / MARK	DRAWING NO.	SHEET	SIZE	TITLE OF DRAWING
*	FCS1012-26-9	1 OF 6	D	BILL OF MATERIAL
*	FCS1012-26-9	2 OF 6	D	EQUIPMENT LAYOUT
*	FCS1012-26-9	3 OF 6	D	ELECTRICAL SCHEMATIC
*	FCS1012-26-9	4 OF 6	D	HALO GROUNDING & DETAILS
*	FCS1012-26-9	5 OF 6	D	CABLE LADDER LAYOUT
*	FCS1012-26-9	6 OF 6	D	SHIPPING/SETUP INSTRUCTIONS
	FCS1012-26-29	1 THRU 7	C	CASTINGS
	L-001-2	1 OF 1	C	LIFTING DETAILS
	T-001-2	1 OF 1	C	TRANSPORTATION DETAILS

**PACK-UP MATERIALS**


(IN ADDITION TO ITEMS FROM PACK-UP INSTRUCTIONS)

ITEM	QTY.	U/M	PART NO.	DESCRIPTION
1				
2	1	EA	-	FIELD SETUP KIT: LIFT LUGS AND BOLTS, WARRANTY/ CARDS, OWNERS MANUAL, SHIMS AND SETUP ITEMS.
3				
4				
5	1	EA	388024-2	CONCRETE TIE DOWN KIT (4 PLATES)
6	1	EA	-	WHITE SILICONE SEALANT #A21130
7	2	EA	-	BUTYL RUBBER
8				
9				
10				

**FIELD SET-UP INSTRUCTIONS**

RESPONSIBLE PARTY		ITEMS CHECKED MUST BE INSTALLED AFTER DELIVERY OF SHELTER. REFER TO OWNER'S MANUALS AND/OR DRAWINGS INDICATED.	REFERENCE ITEM OR DWG#
ANDREW	CUSTOMER		
FIELD CREW	X	TIE-DOWN SHELTER TO FOUNDATION	388024-2
	X	TRANSPORT SHELTER	T-001-2
	X	OFFLOAD SHELTER	L-001-2

SHIPPING SPECIFICATIONS	
BLDG. LENGTH:	12'-6" W/OVERHANGS
BLDG. WIDTH:	10'-6" W/OVERHANGS
OVERALL BLDG. HEIGHT:	9'-11"
APPROX. BLDG. WEIGHT:	25,000
OFFLOADING REQUIREMENTS	
<input type="checkbox"/>	STRAP OFFLOAD: REF. DWG.# L-001-1
<input checked="" type="checkbox"/>	CABLE OFFLOAD: REF. DWG.# L-001-2 FOR CRANE SUPPLIED CABLES, SHACKLES & SPREADER BAR.



CONSTRUCTION DOCUMENTS  
RALEIGH OFFICE

NO. OF STOREY	1	DATE	10/31/96
DRAWN BY	...	CHECKED BY	...
PROJECT NO.	...	SCALE	...
PROJECT NAME	...	DATE	...
<b>ANDREW</b>			
SHIPPING/SET UP INSTRUCTIONS ATT WIRELESS SYSTEMS NORTH CAROLINA REGION			
DWG. NO.	FCS1012-26-9	SCALE	...
SHEET	6	TOTAL SHEETS	6

**APPROVED**  
TER 9/8/92  
TM 9-B-97