



**NOTES:**

- REFER TO SITE SPECIFIC PLANS FOR ACTUAL LOCATION OF TANKS. LOCATION OF UNDERGROUND TANKS MAY VARY DUE TO SITE CONDITIONS AND RESTRICTIONS.
- UNDERGROUND TANKS MAY BE CAST-IN-PLACE OR PRE-CAST CONCRETE. PRE-CAST TANKS SHALL BE PROVIDED WITH GASKET & SEALING KIT. TANKS SHALL BE TESTED FOR LEAKAGE AND SHALL BE PAINTED WITH A CONCRETE SEALER.
- DEPTH OF TANKS WILL DEPEND ON SLOPE AND RUN (DISTANCE) OF 4" Ø PVC DRAIN PIPE. CONSULT RYKO REPRESENTATIVE.
- GENERAL CONTRACTOR SHALL COORDINATE INSTALLATION OF EV-II OPTION SYSTEM WITH RYKO EQUIPMENT INSTALLER.

Date	No.	Revisions	By
<b>ENVIRONMENTALIST II INSTALLATION DETAILS</b>			
Scale	District		
Drawn By			
Checked By	Date		
Approved	No. <b>CW-4</b>		
Do not scale, use dimensions only			