

1/12/95. FIRST PHASE OF SEWER PERMIT → Lots 199-216, 252, 253 (20 total)


— 3/4" WATERLINE SERVICE  
 = 4" SANITARY SEWER SERVICE

ALL WL SHALL BE DIP

PROJECTED SANITARY SEWER FLOW  
 55 LOTS x 280 GPD = 15,400 GPD

**FOR CONSTRUCTION**

- NOTES
- 1) IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY LOCATION OF ALL EXISTING UTILITIES.
  - 2) ALL WORK SHALL BE DONE IN CONFORMANCE WITH TOWN OF CARY STANDARDS AND SPECIFICATIONS.
  - 3) THE LENGTH OF SAG VERTICAL CURVES REDUCED IN ACCORDANCE WITH TOWN OF CARY POLICY STATEMENT No. 13. ADDITIONAL STREET LIGHTS WILL BE REQUIRED TO PROVIDE ADEQUATE SIGHT DISTANCE.
  - 4) THE OWNER SHALL CONTACT AND COORDINATE WITH CP&L TO DEVELOP A STREET LIGHTING PLAN.
  - 5) THE OWNER IS RESPONSIBLE FOR ALL INSTALLATION COSTS ASSOCIATED WITH THE STREET LIGHTING PLAN.



WELLSLEY PHASE 7

UTILITIES

**HUGH J. GILLEECE & ASSOCIATES**  
 875 WALNUT ST SUITE 350 CARY, NC 27511 (919) 469-1101

REVISIONS: 09/28/94-1st SUBMITTAL  
 10/14/94-2nd SUBMITTAL  
 11/08/94-3rd SUBMITTAL  
 12/16/94-STREET NAMES

SHEET: **2**  
 OF