STORM STRUCTURE SUMMARY -- 4/25/90

FROM STR.	TO STR. (TOP*)	DIA (in)	LTH (ft)	S% (est.)	AREA (ac)	'C'	FLOW (cfs)	INVERT DOWNSTRM	INVERT UPSTRM
HW1	CB2 (466.00)	48	65	2.20	1.12	0.85	196.07	440.71	442.14
CB2	CB5 (468.90)	48	363	1.60	0.59	0.85	180.21	442.14	447.95
CB5	CB7 (469.50)	48	110	1.50	0.80	0.85	173.47	447.95	449.60
CB7	MH8 (470.04)	48	143	1.40	0.00	0.85	168.87	449.60	451.60
MH8	CB12 (471.40)	48	95	1.10	0.15	0.85	164.82	451.60	452.64
CB12	CB13 (469.55)	48	92	1.10	0.65	0.85	164.02	452.64	453.66
CB13	CB15A (470.80)	48	224	1.00	1.45	0.85	145.90	453.66	456.40
CB15A	CB16 (470.85)	48	166	0.68	0.81	0.85	113.79	456.40	457.30
CB18	CB17 (+00)	42	29	1.10	0.81	0.85	109.34	457.69	457.91
CB18	*W2 (+1.00)	42	56	0.90	0.98	0.85	98.89	457.81	458.42
Y121	CB19 (473.20)	36	119	0.50	1.45	0.85	44.96	458.72	459.31
CB20	CB21 (475.20)	36	254	0.50	0.15	0.85	30.91	459.31	460.58
CB21	CB22 (473.42)	33	203	0.50	0.53	0.85	38.08	460.58	461.75
CB22	CB23 (473.32)	30	11	2.00	0.38	0.85	33.05	461.85	462.07
CB23	CB24 (472.00)	30	123	0.65	0.55	0.85	30.79	462.07	462.87
CB24	CB25 (471.20)	30	49	0.50	0.65	0.85	27.51	462.87	463.11
CB25	CB26 (471.10)	24	11	2.00	0.55	0.85	23.63	463.31	463.53
CB26	CB27 (470.40)	24	80	0.90	0.44	0.85	20.32	463.53	464.25
CB27	CB28 (470.30)	24	7	2.00	0.42	0.85	17.68	464.25	464.39
CB28	CB29 (471.10)	24	68	0.50	0.37	0.85	15.15	464.39	464.73
CB29	CB40 (473.20)	24	75	0.50	0.83	0.85	12.92	464.73	465.11
CB40	Y141 (477.20)	18	223	0.50	0.13	0.85	9.10	465.31	466.42
Y141	MH42 (479.10)	24	35	3.02	0.71	0.90	4.61	466.52	467.64
CB2	CB3 (466.05)	15	7	2.40	1.12	0.85	9.96	454.98	455.16
CB3	CB4 (466.05)	15	85	1.00	0.85	0.45	3.09	455.15	456.00
CB5	CB6 (468.95)	15	7	1.00	0.59	0.85	3.62	456.93	464.90
MH8	MH9 (473.50)	15	126	1.00	0.00	0.90	0.23	465.24	466.50
MH8	Y110 (481.00)	15	110	1.00	0.08	0.30	3.06	465.90	467.00
Y118	FES11	15	55	1.00	1.00	0.40	2.89	474.45	475.00
CB13	CB14 (469.50)	15	7	1.00	0.65	0.85	3.59	464.93	465.00
CB13	MH110 (474.15)	15	132	1.90	0.51	0.90	6.63	464.36	466.87
MH110	MH111 (474.15)	15	158	1.00	0.51	0.90	3.31	467.07	468.65
CB15A	MH15B (472.45)	18	194	1.60	0.00	0.90	13.42	462.08	465.16
MH15B	Y116A (470.59)	15	40	1.25	0.28	0.90	7.18	465.50	466.00
Y116A	Y116B (474.00)	15	25	1.00	0.04	0.90	5.36	466.10	466.35
MH15B	MH16C (474.15)	15	84	1.00	0.00	0.90	6.24	465.41	466.25
MH16C	MH16D (474.15)	15	112	1.00	0.48	0.90	3.12	467.53	468.65
CB15A	Y117 (470.00)	18	230	2.00	0.03	0.00	0.00	462.50	468.10
Y117	FES43	18	64	0.50	1.00	0.60	15.16	468.18	468.50
Y117	Y144 (FIELD SET)	15	10	3.00	2.50	0.90	10.53	468.70	469.00
CB21	CB22 (473.20)	30	188	1.10	1.30	0.90	49.50	460.08	462.15
CB22	MH22A (473.88)	30	149	1.00	0.00	0.85	33.56	462.45	463.94
MH22A	MH22B (474.41)	24	54	2.40	0.00	0.85	33.56	463.84	465.23
MH22B	MH25 (470.80)	24	81	1.70	0.00	0.85	27.84	463.93	466.28
MH25	CB26 (476.40)	18	26	1.15	0.70	0.85	11.21	467.72	468.02
CB26	Y127 (476.00)	18	288	1.00	0.06	0.85	7.17	468.12	471.00
MH25	CB28 (479.20)	18	197	2.60	0.00	0.85	16.43	465.88	472.00
CB28	Y129 (479.80)	15	96	1.00	0.24	0.85	6.57	472.06	472.96
MH22B	Y124 (473.80)	15	48	1.00	0.02	0.95	5.72	466.00	466.48
CB22	CB23 (474.90)	15	107	1.80	0.73	0.80	4.22	468.07	470.00
CB19	CB20 (461.05)	15	7	5.00	0.81	0.85	4.97	456.52	457.64
CB24	CB65 (466.30)	36	74	1.00	1.10	0.85	54.01	456.44	457.18
CB65	CB66 (464.70)	36	157	1.09	1.10	0.85	57.26	457.18	458.75
CB66	MH114 (472.06)	30	210	1.00	0.00	0.00	31.67	460.25	462.35
MH114	CB67 (473.25)	24	122	1.70	0.29	0.85	31.67	462.35	464.42
CB67	Y168 (478.50)	24	120	0.60	0.30	0.90	11.70	464.52	465.24
Y168	Y169 (478.70)	18	36	1.00	1.50	0.90	9.75	465.64	466.00
CB67	EXISTING Y1	15	178	4.00	2.00	0.90	13.00	465.93	473.05
MH114	MH115 (474.15)	15	93	1.00	0.40	0.90	5.20	466.99	467.92
MH115	MH116 (474.15)	15	86	1.00	0.40	0.90	2.60	468.12	469.00
CB66	CB70 (464.65)	24	7	0.70	1.10	0.85	18.84	459.25	459.30
CB70	CB71 (465.55)	18	126	1.30	0.69	0.85	12.09	459.30	460.94
CB71	CB72 (467.60)	15	97	1.50	0.62	0.85	7.88	460.94	462.40
CB72	CB73 (468.00)	15	75	0.50	0.20	0.85	4.05	462.40	462.77
CB73	CB74 (468.00)	15	46	0.50	0.46	0.85	2.82	462.77	463.00
CB64	CB60 (466.30)	24	4	1.40	0.50	0.85	26.66	460.62	460.73
CB60	CB61 (466.30)	24	62	1.10	0.50	0.85	22.96	460.73	461.41
CB61	CB62 (473.25)	24	272	1.75	0.18	0.85	19.36	461.34	466.30
CB62	MH63 (473.90)	24	86	1.00	2.60	0.93	18.19	466.64	467.50
Y150	CB51 (466.00)	24	78	24.00	0.35	0.85	42.85	438.28	457.00
CB51	CB52 (466.22)	24	36	4.10	0.10	0.85	45.70	457.13	458.59
CB52	CB53 (469.65)	24	35	5.00	0.71	0.85	45.09	458.69	460.79
CB53	MH54 (47 .28)	24	127	1.00	1.60	0.90	19.49	464.43	465.70
MH54	MH52 (473.60)	15	23	4.35	1.40	0.90	9.10	468.00	469.00
CB51	CB55 (468.00)	15	69	1.00	0.50	0.85	3.97	462.90	463.59
CB53	CB56 (470.70)	15	56	1.00	0.45	0.85	2.76	464.34	465.50
CB53	CB57 (469 75)	24	7	3.00	0.71	0.85	18.47	461.29	461.30
CB57	MH58 (472.67)	24	110	3.00	2.30	0.85	14.12	461.50	464.80
Y184	CB85 (467.50)	18	86	1.00	1.00	0.85	10.31	458.15	459.01
CB85	CB86 (465.00)	15	47	1.00	0.40	0.90	4.17	459.01	459.48
CB86	CB87 (464.65)	15	32	1.00	0.28	0.05	1.72	459.48	459.80
EXTXCP	CB90 (458.50)	30	25	0.47	0.13	0.85	17.98	453.18	453.30
CB91	CB91 (464.00)	24	32	1.00	0.80	0.85	14.42	452.35	453.67
CB91	CB92 (466.22)	24	46	8.00	0.75	0.55	12.27	454.10	457.78
CB92	CB93A (462.95)	15	7	1.50	0.75	0.55	7.67	458.08	458.1
CB93A	CB93B (463.45)	15	44	0.50	0.50	0.85	3.87	458.18	458.40
EX	CB88 (471.75)	15	160	1.00	0.70	0.85	4.30	464.46	466.00
---	CB89 (472.80)	---	--	--	---	---	---	---	464.50
FES90	CB91 (464.10)	30	154	1.10	0.37	0.85	42.65	445.39	448.95
CB91	CB92 (464.10)	24	39	2.20	0.35	0.85	40.38	447.49	448.35
CB92	CB93 (462.50)	24	27	3.00	0.50	0.85	38.23	450.05	450.86
CB93	CB94 (462.50)	15	114	1.00	0.80	0.85	4.91	456.36	457.50
CB93	CB95 (462.50)	24	110	1.00	0.80	0.85	21.79	451.66	452.16
CB95	CB96 (462.50)	24	112	1.00	0.58	0.85	16.66	452.16	453.28
CB96	CB97 (459.75)	18	28	1.65	0.50	0.85	13.50	453.78	454.24
CB97	CB98 (461.70)	15	70	2.80	0.60	0.85	10.43	454.54	456.50
CB98	CB99 (463.70)	15	50	3.70	0.50	0.85	3.07	456.60	459.80
CB98	CB100 (462.09)	15	16	1.00	0.66	0.85	3.68	456.80	457.09
CB93	MH112 (474.15)	15	315	2.80	0.51	0.90	6.63	457.43	466.25
MH112	MH113 (474.15)	15	158	1.00	0.51	0.90	3.31	467.97	468.55
Fx	CB102 (444.10)	15	20	1.00	0.50	0.85	5.83	430.30	438.50
CB102	CB103 (448.40)	15	128	3.90	0.45	0.85	2.76	438.51	443.50

* TOP ELEVATION *

TOP BACK OF CURB FOR CATCH BASINS

TOP OF CASTING FOR MANHOLES AND YARD INLETS

SEEDING SCHEDULE
(REVISED 1-1-88)

SHOULDERS, SIDE DITCHES, SLOPES (MAX. 3:1)

DATE	TYPE	PLANTING RATE
AUG 1-NOV 1	TALL FESCUE	300 LBS./ACRE
NOV 1-MAR 1	TALL FESCUE	300 LBS/ACRE
	1 MERLIN RYE	25 LBS/ACRE
MAR 1-APRIL 15	TALL FESCUE	300 LBS/ACRE
APRIL 15-JUNE 30	HULLED COMMON BERMUDAGRASS	25 LBS/ACRE
JULY 1-AUG 15	TALL FESCUE plus ***BROWNTOP MILLET	120 LBS/ACRE 35 LBS/ACRE
	***or SORGHUM-SUDAN HYBRIDS	30 LBS/ACRE

SLOPES (>1:1 TO 2:1)

MAR 1-JUNE 1	SERICEA LESPEDEZA (SCARIFIED)	50 LBS/ACRE
(MAR 1-APR 15)	plus TALL FESCUE	120 LBS/ACRE
(MAR 1-JUNE 30)	or plus WEEPING LOVEGRASS	10 LBS/ACRE
(MAR 1-JUNE 30)	or plus HULLED COMMON BERMUDAGRASS	25 LBS/ACRE
JUNE 1-SEPT 1	***TALL FESCUE plus ***BROWNTOP MILLET or ***or SORGHUM-SUDAN HYBRIDS	120 LBS/ACRE 35 LBS/ACRE 30 LBS/ACRE
SEPT 1-MAR 1	SERICEA LESPEDEZA (UNHULLED-UNSCARIFIED) plus TALL FESCUE plus KRALED RYE	70 LBS/ACRE 120 LBS/ACRE 25 LBS/ACRE

CONSULT CONSERVATION ENGINEER OR SOIL CONSERVATION SERVICE FOR ADDITIONAL INFORMATION CONCERNING OTHER ALTERNATIVES FOR VEGETATION OF DENUDED AREAS. THE ABOVE VEGETATION ALTERNATIVES WERE SELECTED WELL UNDER LOCAL CONDITIONS. OTHER SEEDING RATE COMBINATIONS ARE POSSIBLE.

*** TEMPORARY - RESEED ACCORDING TO OPTIMUM SEASON FOR DESIRED PERMANENT VEGETATION. DO NOT ALLOW TEMPORARY COVER TO GROW OVER 12" IN HEIGHT BEFORE MOWING, OTHERWISE FESCUE MAY BE SHADED OUT.

SEEDBED PREPARATION

1. CHISEL COMPACTED AREAS AND SPREAD TOPSOIL OVER ADVERSE SOIL CONDITIONS.
2. CULTIVATE ENTIRE AREA TO A DEPTH OF 6".
3. REMOVE ALL LOOSE ROCK, ROOTS, AND OTHER OBSTRUCTIONS LEAVING SURFACE REASONABLY SMOOTH AND UNIFORM.
4. APPLY AGRICULTURAL LIME, FERTILIZER, AND SUPERPHOSPHATE (APPROXIMATELY AT RATES SHOWN BELOW) AND MIX WITH SOIL.
5. CONTINUE TILLAGE UNTIL A WELL-PULVERIZED, FIRM REASONABLY UNIFORM SEEDBED IS PREPARED TO A DEPTH OF 4 TO 6 INCHES.
6. SOW ON FRESHLY PREPARED SEEDBED AND COVER SEED LIGHTLY WITH SEEDING EQUIPMENT OR CULTIPACK AFTER SEEDING.
7. MULCH WITH STRAW AND ANCHOR.
8. INSPECT ALL SEEDED AREAS AND MAKE NECESSARY REPAIRS OR RESEEDINGS WITHIN THE PLANTING SEASON, IF POSSIBLE. IF STAND SHOULD BE OVER 80% DAMAGED, RE-ESTABLISH, FOLLOWING ORIGINAL LIME, FERTILIZER AND SEEDING RATES.
9. CONSULT CONSERVATION INSPECTOR ON MAINTENANCE TREATMENT AND FERTILIZATION AFTER PERMANENT COVER IS ESTABLISHED.

APPLICATION RATES:

AGRICULTURAL LIMESTONE - 2 TONS/ACRE
FERTILIZER (10-10-10) - 1000-1200 LBS/ACRE
SUPERPHOSPHATE (20% ANALYSIS) - 500 LBS/ACRE
MULCH (SMALL GRAIN STRAW) - 80 BALES/ACRE
ANCHOR TACK - LIQUID ASPHALT, 400 GALS/ACRE EMULSIFIED ASPHALT, 300 GALS/ACRE

NOTE: ALL CONSTRUCTION IS TO BE PERFORMED IN ACCORDANCE WITH CURRENT TOWN OF CARY STANDARDS AND SPECIFICATIONS.

CONSTRUCTION SEQUENCE

1. OBTAIN GRADING PERMIT.
2. INSTALL ALL EROSION CONTROL MEASURES AS SHOWN.
3. OBTAIN CERTIFICATE OF COMPLIANCE THROUGH ON-SITE INSPECTION BY LOCAL EROSION CONTROL ENGINEER.
4. PROCEED WITH GRADING.
5. CLEAN SEDIMENT BASINS WHEN HALF FULL.
6. UPON CONSTRUCTION OF EACH DRAINAGE STRUCTURE BOX INSTALL SEDIMENT FILTER AS INDICATED IN DETAIL AND MAINTAIN UNTIL AT SUCH TIME THAT BASE COURSE IS IN PLACE.
7. SEED AND MULCH DENUDED AREA WITHIN 30 DAYS AFTER FINISHED GRADES ARE ESTABLISHED.
8. MAINTAIN SOIL EROSION CONTROL MEASURES UNTIL PERMANENT GROUND COVER IS ESTABLISHED.
9. UPON FINAL APPROVAL BY EROSION CONTROL ENGINEER, REMOVE SOIL EROSION CONTROL MEASURES AND STABILIZE THESE AREAS.



Wm. G. Daniel & Assoc.
Engineering Planning
Landscape Architecture

NORTH CAROLINA REGISTERED SEAL 13039 ENGINEER CLIFFORD GLENN SMITH
3/1/90

NORTH CAROLINA REGISTERED SEAL 361 LANDSCAPE ARCHITECT HAROLD ROY SMITH, JR.

Revisions

2) MARCH 19, 1990 - TOC FIRST REVIEW

3) APRIL 9, 1990 - REVISED STORM CHARTS

4) APRIL 25, 1990 - REVISED STORM CHARTS

NOT ISSUED FOR CONSTRUCTION

Project

CARY VILLAGE MALL

GRADING, UTILITIES, EROSION CONTROL

Date

March 1, 1990

Scale

1" = 50'

Sheet

U1