



- NOTES FOR CONSTRUCTION**
- 1) IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY LOCATION OF ALL EXISTING UTILITIES.
  - 2) ALL WORK SHALL BE DONE IN CONFORMANCE WITH TOWN OF CARY STANDARDS AND SPECIFICATIONS.
  - 3) SEWER FLOW 7,200 GPD (100GPD/ROOM x 72 ROOMS)
  - 4) 6" WATERLINE SHALL BE D.I.P.
  - 5) OPEN CUT SHALL BE COORDINATED WITH WACHOVIA BANK PRIOR TO CONSTRUCTION.



SCALE 1" = 20'  
 0 20 40

**STUDIO PLUS**

**UTILITIES**

**Hugh J. Gilleece and Associates**  
 875 Walnut St. Suite 350 Cary, NC ph(919)469-1101 fax(919)460-7637

Revisions:	Designed by: TS	Sheet: 2
	Drawn by: TS	
	Project: 4026.00	